



Fillmore County Highway Department

909 Houston Street NW, Preston, MN 55965

(P) (507) 765-3854
(F) (507) 765-4476

RONALD GREGG, P.E.
COUNTY ENGINEER

BRENT KOHN
MAINTENANCE SUPERINTENDENT

September 4, 2018

ADDENDUM No. 2

To: Plan Holders

From: Ronald Gregg P.E.

Project No.: SAP 023-601-029

Dear Plan Holder: Fillmore County has elected to purchase the Floor Drains Type B706 to help expedite the bridge construction of Bridge No. 23595. Change were made to the Schedule of Prices to reflect installation only, Lump Sum item 2402.601.

- Schedule of Prices, revised Dated 9-4-2018

The revisions are to be used for bidding and the revised documents shall be used in the bidding packet.

PLEASE ACKNOWLEDGE THIS ADDENDUM ON YOUR BID DOCUMENTS!

Sincerely, Ronald Gregg PE
Fillmore County Engineer

A handwritten signature in blue ink, appearing to read "Ronald Gregg".

507-765-3854

E-mail rgregg@co.fillmore.mn.us

BIDDER MUST FILL IN UNIT PRICES IN NUMERALS, MAKE EXTENSION FOR EACH ITEM, AND TOTAL. FOR COMPLETE INFORMATION CONCERNING THESE ITEMS, SEE PLANS AND SPECIFICATIONS, INCLUDING SPECIAL PROVISIONS.

SPECIFICATION OR ITEM NO.	ITEM DESCRIPTION	UNIT OF MEASURE	APPROX QUANTITIES	UNIT PRICE		AMOUNT	
				DOLLARS	CTS.	DOLLARS	CTS.
PARTICIPATING ITEMS							
2021.501	MOBILIZATION	LUMP SUM	1				
2104.503	REMOVE PIPE CULVERTS	LIN FT	33				
2104.503	SAWING BITUMINOUS PAVEMENT (FULL DEPTH)	LIN FT	48				
2104.504	REMOVE BITUMINOUS PAVEMENT	SQ YD	2064				
2105.507	SELECT GRANULAR BORROW MOD 10% (CV) (P)	CU YD	626				
2105.507	COMMON BORROW (LV)	CU YD	1301				
2105.507	COMMON EXCAVATION	CU YD	679				
2118.507	AGGREGATE SURFACING (CV) CLASS 5	CU YD	1022				
2301.604	CONCRETE PAVEMENT (SPECIAL)	SQ YD	75				
2401.503	TYPE S (TL-4) BARRIER CONCRETE (3S52) (P)	LIN FT	155				
2401.507	STRUCTURAL CONCRETE (3B52) (P)	CU YD	57				
2401.508	REINFORCEMENT BARS (EPOXY COATED) (P)	POUND	25470				
2401.508	REINFORCEMENT BARS (STAINLESS-75KSI) (P)	POUND	420				
2401.601	SLOPE PREPARATION	LUMP SUM	1				
2401.601	STRUCTURE EXCAVATION	LUMP SUM	1				
2401.618	BRIDGE SLAB CONCRETE (3YHPC-M) (P)	SQ FT	1957				
2402.601	INSTALL 2 FLOOR DRAINS TYPE B706	LUMP SUM	1				
2402.502	ELASTOMERIC BEARING PAD TYPE 1	EACH	8				
2405.601	INSTALL PRESTRESSED CONCRETE BEAMS 27M	LUMP SUM	1				
2406.503	EXPANSION JOINTS, DESIGN E8H	LIN FT	68				
2406.504	BRIDGE APPROACH PANELS	SQ YD	153				
2442.501	REMOVE EXISTING BRIDGE	LUMP SUM	1				
2452.502	STEEL H-TEST PILE 40 FT LONG 10"	EACH	2				
2452.502	PILE TIP PROTECTION 10"	EACH	8				

BIDDER MUST FILL IN UNIT PRICES IN NUMERALS, MAKE EXTENSION FOR EACH ITEM, AND TOTAL. FOR COMPLETE INFORMATION CONCERNING THESE ITEMS, SEE PLANS AND SPECIFICATIONS, INCLUDING SPECIAL PROVISIONS.

SPECIFICATION OR ITEM NO.	ITEM DESCRIPTION	UNIT OF MEASURE	APPROX QUANTITIES	UNIT PRICE		AMOUNT	
				DOLLARS	CTS.	DOLLARS	CTS.
2452.603	STEEL H-PILING 10"	LIN FT	180				
2501.502	18" GS PIPE APRON	EACH	4				
2501.503	18" CS PIPE CULVERT	LIN FT	86				
2502.501	DRAINAGE SYSTEM TYPE (B910)	LUMP SUM	1				
2511.504	GEOTEXTILE FILTER TYPE 7	SQ YD	535				
2511.507	RANDOM RIPRAP CLASS V	CU YD	390				
2554.502	END TREATMENT-TANGENT TERMINAL	EACH	4				
2554.503	TRAFFIC BARRIER DESIGN TYPE 31	LIN FT	300				
2554.503	TRAFFIC BARRIER DESIGN TRANSITION TYPE 31	LIN FT	100				
2563.601	TRAFFIC CONTROL	LUMP SUM	1				
2573.503	FLOTATION SILT CURTAIN TYPE MOVING WATER	LIN FT	180				
2573.503	SILT FENCE, TYPE MS	LIN FT	1650				
2575.501	TURF ESTABLISHMENT	LUMP SUM	1				
2575.504	EROSION CONTROL BLANKETS CATEGORY 3N	SQ YD	2380				
2575.505	RAPID STABILIZATION METHOD 1	ACRE	0.5				

SAP 023-601-029 TOTAL: \$ _____

BIDDER NAME _____

BIDDER ADDRESS _____

BIDDER PHONE _____

BIDDER SIGNATURE _____

DATE: _____